


Notes

1. Flaggers may hold traffic for a maximum of 20 minutes
2. Flaggers shall assist pedestrians through flagged intersections
3. Flaggers shall have light plants during non-daylight hours and maintain high levels of visibility at all times
4. Mount signs with jersey barrier brackets as needed
5. Maintain 12' minimum lane width for auto traffic at all times
6. Cone spacing at 45 MPH | Taper = 40' | Tangent = 40' | Corner/Access/Bike/Ped = 10'
7. All traffic control shall adhere to current MUTCD & OTTCH guidelines
8. Adjust to field conditions




Legend

- 48" x 48" Signs w/ Flags
- 28" Cones
- Parking Lane
- Work Zone
- Flagger
- Pilot Car
- Cone Pick Up Vehicle
- Oversized Load

Equipment List

- 3 Road Work Ahead
- 2 Be Prepared to Stop
- 2 Flagger Ahead
- 15 28" Cones
- 2 Flaggers with Radios
- 2 Cone Mounted - Wait for Pilot Car
- 1 Cone Pick Up Vehicle



D&H PLAN #13064-1  
October 1, 2025

Prepared By: Mike James  
Office: (503) 232-2488  
Email: plans@d-hflagging.com

Contractor: Demase Warehouse Systems, Inc  
Contact Person: Alan Jones  
Phone: 903-504-3910  
Email: alan.jones@demase.com  
Job Location: OR-212 & SE 162 Ave  
City, State: Damascus, OR  
Type of Work: Oversized Load Transport  
Job Duration: 20 Minutes