


Notes

1. Flaggers shall have light plants during non-daylight hours and maintain high levels of visibility at all times
 2. Flaggers shall assist pedestrians through flagged intersections
 3. Spotter shall assist pedestrians through work zone
 4. Maintain 11' minimum lane width for auto traffic at all times
 5. Cone spacing at 25 MPH | Taper = 20' | Tangent = 20' | Corner/Access/Bike/Ped = 10'
 6. All traffic control shall adhere to current MUTCD & PBOT Manual guidelines
 7. Adjust to field conditions



D&H
FLAGGING

D&H PLAN #13115-1
October 17, 2025

Prepared By: Rory Homan
Office: (503) 232-2488
Email: plans@d-hflagging.com

Contractor: SavATree
Contact Person: Angela Fajardo
Phone: 503-645-2242
Email: afajardo@savatree.com
Job Location: 366 N Lotus Isle Dr
City, State: Portland, OR
Type of Work: Tree Pruning
Job Duration: 1 Day