



Notes

- 1. Flaggers shall assist pedestrians through flagged intersections
- 2. Flaggers shall have light plants during non-daylight hours and maintain high levels of visibility at all times
- 3. Maintain 10' minimum lane width for auto traffic at all times
- 4. Cone spacing at 25 MPH | Taper = 20' | Tangent = 20' | Corner/Access/Bike/Ped = 10'
- 5. Adjust devices so that residential and/or business entrances/exits are not affected
- 6. All traffic control shall adhere to current MUTCD & OTTCH guidelines
- 7. Adjust to field conditions

Equipment List

- 4 Road Work Ahead
- 4 Be Prepared to Stop
- 4 Flagger Ahead
- 30 28" Cones
- 3 Flaggers with Radios



Legend

- 48" x 48" Signs w/ Flags
- 28" Cones
- Parking Lane
- Work Zone
- Manhole Location
- Flagger



**D&H
FLAGGING**
EST. 1988

D&H PLAN #13198-1
November 20, 2025

Prepared By: Adam Albers
Office: (503) 232-2488
Email: plans@d-hflagging.com

Contractor: SFE Global Inc
Contact Person: Dylan Carvin
Phone: 928-606-9469
Email: Dylan.Carvin@sfe-global.com
Job Location: SE Rupert Dr & SE Park Entrance St
City, State: Oak Grove, OR
Type of Work: Flow Monitoring Site Installation
Job Duration: 2-4 Hours Per Location